BRUHAT BANGALORE MAHANAGARA PALIKE

Executive Engineer, Rajarajeshwarinagara Division, Rajarajeshwarinagara Zone, Bangalore

MODIFIED SCHEDULE-B

Name of Work: Community Property Maintenance (Including Parks) in JP Park in Ward No.17

Sl.No	App. Qty	Description	Unit	Approved Rates quoted by Sri.Ishwar N Naik	
				In Figures	In Words
1	0.00	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint, including cost of materials, labour, HOM complete as per specifications. (P. 266, It.No.37.3)	Sqm	727.00	Rupees Seven Hundred Twenty Seven Only
2	0.00	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer-in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) including cost of materials, labour, HOM complete as per specifications. (P. 266, It.No.37.2)	Cum	874.00	Rupees Eight Hundred Seventy Four Only
3	0.00	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint, including cost of materials, labour, HOM complete as per specifications. (P. 266, It.No.37.4)	Cum	415.00	Rupees Four Hundred Fifteen Only
4	0.00	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.. (P. 123, It.No.15.74)	Cum	96.00	Rupees Ninety Six Only
		EIRL			
E-1	95.04	Removing & Refixing stone slabs of drains and pointing in C.M (1:3) (P. 27, It.No.5.33	Sqm	106.76	Rupees One Hundred Six And Paise Seventy Six Only

Signature of the Contractor

Executive Engineer
RR Nagara Divisi

Scanned with CamScanner

Item	Qty	Description	Unit	Approved Rates quoted by Sri.Ishwar N Naik	
				In Figures	In Words
	105.60	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P. 143, It.No.19.1)	Sqm	132.18	Rupees One Hundred Thirty Two And Paise Eighteen Only
E-3	140.80	KSRB 5-14: Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 - do - with solid concrete blocks of size 400x200x200mm (P. 27, It.No.5.26.1)	Sqm	978.12	Rupees Nine Hundred Seventy Eight And Paise Twelve Only
E-4	63.36	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. - do - 10 cms thick (P. 27, It.No.5.31.2)	Sqm	927.28	Rupees Nine Hundred Twenty Seven And Paise Twenty Eight Only

Harishappa. R.
Signature of the Contractor

Executive Engineer
RR Nagara Division, RR Nagara Zone
BBMP, Bangalore

Harishappa. R.
Signature of the Contractor

Executive Engineer
RR Nagara Division

Scanned with CamScanner